


**INSTALLATION EXAMPLE**



**Rear load door detail:**

1. Hinge rear door panels constructed of heavy-gauge steel power coated postal grey.
2. Latch mechanism secures rear doors - this is the USPS approved standard design.
3. No USPS arrow lock required for rear doors.

**Installation requirements specified in USPS STD-4C include:**

1. At least one customer compartment shall be positioned less than 48" from the finished floor.
2. No parcel locker (interior bottom shelf) shall be positioned less than 15" from finished floor.
3. No patron (tenant) lock shall be positioned more than 67" above finished floor.
4. No customer compartment (interior bottom shelf) shall be positioned less than 28" from finished floor.

PRODUCT SERIES: VERSATILE™ 4C SUITE I  
REAR LOAD

MODEL	4CIT-4R	REV	
SCALE	NONE	DATE	7/28/2008
DRAWING NUMBER	4CAT14RCS	DRAWN BY	SHEET
		AFD	1 OF 1

by Auth Florence

**The Mailbox Works**  
[www.MailboxWorks.com](http://www.MailboxWorks.com)  
 800.824.9985  
 info@mailboxworks.com