


## Notes:

- Designed to mount Florence Versatile<sup>™</sup> 4C mailbox single column 11-High Suite modules (sold separately).
- 2. For use with front loading modules only.

PRODUCT SERIES:	VERSATILE™ 4C SURFACE MOUN	RSATILE™ 4C SURFACE MOUNT COLLAR				
		MODEL	SM11S	REV	В	
		SCALE	NONE	LAS 7	T REV DATE <b>7/02/2014</b>	
		DRAWIN	IG NUMBER		DRAWN BY	
			SM11SCS		TNS	

## versatile<sup>TM</sup> 4C Mailbox, 4C11S-09



## COMPARTMENT CHART

DESCRIPTION	COMPARTMENT	COMPARTMENT SIZE	QTY.
MAILBOX	MB1	3" H x 12" W x 15" D	9
OUTGOING MAIL	OM2	6-1/2" H x 12" W x 15" D	1

## Notes:

- 1. This module meets the USPS STD-4C requirements for installation defined below when the mailbox is installed per the dimensions provided on this drawing.
  - a. At least one customer compartment shall be positioned less then 48" above finished floor (AFF).
  - b. No parcel locker (interior bottom shelf) shall be positioned less than 15" AFF.
  - c. No patron (tenant) lock shall be positioned more than 67" AFF.
  - d. No customer compartment (interior bottom shelf) shall be positioned less than 28" AFF.
  - e. The USPS Arrow lock shall be positioned 36"- 48" AFF.
- 2. This 4C mailbox can also be used for private applications.
- 3. The rough opening width for multi-unit 4C installations is provided using the Florence configurator: www.florencemailboxes.com/configurator.

PRODUCT SERIES: VERSATILETM 4C FRONT LOAD MAILBOX

MODEL 4C11S-09		REV	Е
SCALE	NONE	LAS	T REV DATE 07/02/19
DRAWING	NUMBER		DRAWN BY
4C	11S-09CS		RAK