


versatile™ 4C Mailbox, 4C06S-04



COMPARTMENT CHART

| DESCRIPTION   | COMPARTMENT | COMPARTMENT SIZE            | QTY. |
|---------------|-------------|-----------------------------|------|
| MAILBOX       | MB1         | 3\" H x 12\" W x 15\" D     | 4    |
| OUTGOING MAIL | OM2         | 6-1/2\" H x 12\" W x 15\" D | 1    |

PRODUCT SERIES: VERSATILE™ 4C FRONT LOAD MAILBOX



|                |            |               |   |
|----------------|------------|---------------|---|
| MODEL          | 4C06S-04   | REV           | B |
| SCALE          | NONE       | LAST REV DATE |   |
| DRAWING NUMBER | 4C06S-04CS | DRAWN BY      |   |

- Notes:
- This module meets the USPS STD-4C requirements for installation defined below when the mailbox is installed per the dimensions provided on this drawing.
    - At least one customer compartment shall be positioned less than 48" above finished floor (AFF).
    - No parcel locker (interior bottom shelf) shall be positioned less than 15" AFF.
    - No patron (tenant) lock shall be positioned more than 67" AFF.
    - No customer compartment (interior bottom shelf) shall be positioned less than 28" AFF.
    - The USPS Arrow lock shall be positioned 36"-48" AFF.
  - This 4C mailbox can also be used for private applications.
  - The rough opening width for multi-unit 4C installations = (the sum of all actual unit widths) - 1 1/8".