


# Versatile™ 4C Mailbox, 4C11S-09



COMPARTMENT CHART

| DESCRIPTION   | COMPARTMENT | COMPARTMENT SIZE         | QTY. |
|---------------|-------------|--------------------------|------|
| MAILBOX       | MB1         | 3" H X 12" W X 15" D     | 9    |
| OUTGOING MAIL | OM2         | 6-1/2" H X 12" W X 15" D | 1    |

PRODUCT SERIES: VERSATILE™ 4C FRONT LOAD MAILBOX



MODEL 4C11S-09

SCALE NONE

DRAWING NUMBER

4C11S-09CS

REV D

LAST REV DATE

DRAWN BY

- Notes:
- This module meets the USPS STD-4C requirements for installation defined below when the mailbox is installed per the dimensions provided on this drawing.
    - At least one customer compartment shall be positioned less than 48" above finished floor (AFF).
    - No parcel locker (interior bottom shelf) shall be positioned less than 15" AFF.
    - No patron (tenant) lock shall be positioned more than 67" AFF.
    - No customer compartment (interior bottom shelf) shall be positioned less than 28" AFF.
    - The USPS Arrow lock shall be positioned 36"-48" AFF.
  - This 4C mailbox can also be used for private applications.
  - The rough opening width for multi-unit 4C installations = (the sum of all actual unit widths) - 1/8".